

## Reefer Monitoring Service Tender

1- Required service description & pricing sheet :

Sr.	Item	Item Description	Unit Price	Comment
1	1012564	SV-Monitoring/ Day		Reefer /Day
2	1012566	SV-Data Retrieval		
3	1012567	SV-Change the power plug		Per plug
4	1012568	SV-Repair of power cable		
5	1012569	SV-Clean Condenser		
6	1012570	SV-Full PTI		per reefer
7	1012571	SV-Short PTI		per reefer
8	1012572	SV-Gen set for Full PTI		exclude fuel
9	1012573	SV-Gen set for Short PTI		exclude fuel
10	1012577	SV-Plugging/ Unplugging Inspection. etc.)		per reefer
11	1012578	SV-Inspection & certification (CSC)		by IICL standard
12	1012580	SV-Container Inspection (condition, On Off Hire)		per container
13	1012581	SV-Dry container Repair		Man per Hr.
14	1012582	SV-Reefer Container repair		Man per Hr.
15	1012583	SV-Gen Set Rental		Per trip

2- Scope of Service:

- Provide all reefers service related to handling and monitoring of reefer temperature
- Provide repairing service for damaged containers

### 3- Terms of service :

- a- Reefer contractor shall plug-in and unplug temperature-controlled units within 30 minutes of nomination by AICT company at the power points provided on AICT company terminals and will carry out data downloads of all containers when unplugged ready for shipment, either import or export. The cost of each download is documented in the attached spreadsheet and retrieval of information for any claim against the company provided free of charge to AICT company.
- b- Reefer contractor shall unplug import temperature-controlled units for collection by outside haulage companies or AICT company vehicles for the purpose of inspection in accordance with instructions from the unit operator or AICT company.
- c- Reefer contractor shall monitor the movement of all temperature-controlled units and ensure that no unit is left unplugged for more than 2 hours.
- d- Reefer contractor shall unplug export temperature-controlled units for movement to vessels in accordance with instructions from AICT company.
- e- Reefer contractor shall monitor all temperature-controlled units at intervals not exceeding 6 hours and at least four times every twenty-four hours to ensure correct operation and for any signs of damage (this is a minimum requirement). The requirement time of each monitoring call shall be recorded using manual logbook system provided by the reefer contractor.
- f- Reefer contractor will notify the unit operator and AICT company of fault/damage, and if the unit is operating at a temperature other than that stated on the list provided by AICT company.
- g- Reefer contractor shall notify AICT company immediately if any plug-in points are found to be damaged or unserviceable.
- h- Reefer contractor shall undertake minor repairs to temperature-controlled units if authorized by AICT company at the points on board vessels.
- i- Reefer contractor shall attend on board vessels to plug and unplug temperature-controlled units were instructed to do so by AICT company and inspect those containers due to be discharged for damage and temperature settings.
- j- Reefer contractor is obliged to provide two caravans for both Alexandria and Eldekhliela terminals (one for each terminal) for storing his equipment and materials.
- k- Reefer contractor shall provide sufficient trained and skilled labor to always fulfill its obligations under this clause and who will undertake their duties in accordance with the current code of practice and general byelaws issued by AICT company.
- l- Reefer contractor shall be responsible for all acts of his employers, agents, and subcontractors.
- m- Reefer contractor shall comply with AICT company security and safety requirements.
- n- Reefer contractor shall complete and retain records on all functions carried out on behalf of AICT company both on paper and computer data base for integration and transfer to AICT company upon request.